Client: ConocoPhillips Australia Business Unit (ABU)

Document: Storyboard for Management of Change (MOC) Awareness of Downstream Operations (DSO)

Version History:

| Version No. | Edited By | Date | Remarks |
|-------------|---------------|-----------------|-----------------------|
| 001 | Sheetal Mehta | January 3, 2025 | Framework SB creation |
| 002 | Sheetal Mehta | March 13, 2025 | SB creation |
| 003 | Sheetal Mehta | March 28, 2025 | SB updates |


Please refer to conocophillips_ABU Management of Change (MOC) Awareness Module_ 2024 Review_ FINAL_for Learning Factor.pptx for images.

Contents

| splash screen> | 3 |
|---|----|
| ntroduction | 4 |
| earning Objectives | 6 |
| Nanagement of Change (MOC) | 7 |
| Standard MOC (SMOC) for Engineering Changes | 11 |
| Operational Deviations MOC (ODMOC) | 24 |
| Document MOC (DMOC) | 34 |
| Organisational MOC (ORGMOC) | 39 |
| luiz | 45 |
| hank you | 47 |

| Topic | | Management of Change (MOC) Awareness | s for Downstream Operations (DSO) | Screen type | Image |
|----------|--|--|---|---|--|
| Screen T | Screen Title <splash screen=""></splash> | | | Screen number | 010A |
| No. | Audio/VO | | On Screen Text | Visuals and Develo | opment instructions |
| 1. | Welcome to the C (MOC) Awareness | onoco Phillips Management of Change training. | Management of Change (MOC) Awareness Training | Create a splash scr 402376873 (remov | OPTIONS OF THE PROPERTY OF THE |
| 2. | Click on the start | button to begin. | Start | | |

| Topic | | Management of Change (MOC) Awareness | for Downstream Operations (DSO) | Screen type | Image |
|----------|------------------|---|---------------------------------|---|----------------------------------|
| Screen T | itle | Introduction | | Screen number | 010 |
| No. | Audio/VO | | On Screen Text | Visuals and Development instructions | |
| 1. | | ic industrial landscape, the ability to ge change is crucial for maintaining rity and safety. | | Display the image with camera spanning from left to right slowly in sync with VO. APLNG Image of whole site and ship in forefront. | |
| 2. | approach that en | t of Change (MOC) process is a structured sures all modifications to processes, erations are thoroughly evaluated and | | | ser view of the building. |
| 3. | | equip you with the knowledge and skills stand Management of Change (MOC). | | • | nterior shot of the control room |



| Topic | Topic Management of Change (MOC) Awareness to | | for Downstream Operations (DSO) | Screen type | Image and text |
|----------|--|--|---|---|---------------------|
| Screen T | Screen Title Learning Objectives | | | | 020 |
| No. | Audio/VO | | On Screen Text | Visuals and Devel | opment instructions |
| 1. | | | By the end of this module, you will be able to: Comprehend the purpose and importance of Management of Change (MOC) Understand the four categories of MOC Learn the key steps in the MOC process at ABU Identify examples of change | Display OST in syn Design Learning C | |
| | | | <next></next> | | |

| Topic | | Management of Change (MC | C) Awareness for Downstream Operations (DSO) | Screen type | Blended |
|----------|---|---|---|---|--|
| Screen T | itle | Management of Change (MO | C) | Screen number | 030 |
| No. | Audio/VO | | ON SCREEN TEXT | Visuals and Develo | opment instructions |
| 1. | What is MOC? | | What is MOC? | Display OST. Typography Global for all quest | tions. |
| 2. | making sure that | Change (MOC) is about any changes to the plant, el, or procedures are carefully | Management of Change (MOC) | Create similar anim given below for VC Shutterstock image (Video for reference) | nated icon cloud using icons). e id: 1106263299 |
| 3. | Minimise situations temporar process o configura Ensure pr | the risk of hazardous that could result from y and permanent changes to perations and / or facility tion. cocess changes or facility ions do not compromise the | It's crucial to assess these changes to: Minimise the risk of hazardous situations from changes to process operations or facility configuration Ensure process changes or facility modifications do not compromise the safeguards built into the design or introduce unknown hazards Identify any potential operational risks introduced by the change | Display OST in synd Infographic. | with VO. |

| | safeguards built into the design or introduce unknown hazards. Identify any potential operational risks introduced by the change. Ensure that these risks are managed as far as is reasonably practicable and throughout the entire lifecycle of the change, including initiation, implementation, and close out. | Ensure that these risks are managed as far as is reasonably practicable and throughout the entire lifecycle of the change | |
|----|---|--|---|
| 4. | | MOC provides for identification, risk assessment, authorisation, communication and documentation of changes in order to avoid potential major incidents or other unwanted operational incidents. | Refresh screen. Typography: Highlight with a bold font and a different colour. Use a border or background shading to make OST stand out. |
| 5. | All changes, whether they are permanent, temporary, or urgent, must be properly managed and conform to the relevant MOC procedures. | All changes must be properly managed and conform to the relevant MOC procedures. | Display OST in sync with VO. 2427685747 |
| 6. | Let's take a look at MOC Process Workflow. The flow chart guides you through the broad steps of a process workflow for Management of Change. The sub points are examples depending on the type of MOC initiated. | MOC Process Workflow | Clickable infographic flip card activity. Display OST and the respective icons on the front. 2519013597(Remove numbers) |

| | | | 1688952 | 1048277 | 2227791 | 1369705 | |
|-----|---|--|--|--|--|------------------------|--|
| | | | 019 (for | 092 (for | 681 (for | 1369705 136 (for | |
| | | | 1 st bullet | 2 nd bullet | 3 rd bullet | 4 th bullet | |
| | | | point) | point) | | | |
| | | 01 | point | point | point) | point) | |
| | Create | | | | | | |
| 7. | | Initiate Type of MOC required including all relevant | | | | | |
| | document/ design documentation attached | | | | | | |
| | | Evaluate | | | | | |
| 8. | | Discipline Reviews to assess that changes are | | | | | |
| | | adequately engineered, meet applicable design | | | | | |
| | | standards and satisfy the intent and basis of the | | | | | |
| | | required change | | | | | |
| | | Execute | | | | | |
| 9. | | Pre-Start Safety Review (PSSR) Requirement | | | | | |
| | | Approval to Start-Up (Operations) | | | | | |
| | | Record Start-Up Date | | | | | |
| | | Document Approval | | | | | |
| | | Closeout | | | | | |
| 10. | | Upload of affected Redlines/Blacklines | | | | | |
| | | Verify all Docs updated and latest revision on | | | | | |
| | | ODMS | | | | | |
| | | Activity Ends | | | | | |
| 11. | For more information or assistance regarding | For more information regarding the MOC workflow, | | | d 'ABU East | OMS' in | |
| | the MOC workflow, contact the Process Safety | contact the Process Safety Team or visit the Process Safety | sync with V | <i>O</i> . | | | |
| | Team or visit the Process Safety Engineering | Engineering SharePoint site to access FAQs and guides. | Guide to ac | cess the Prod | cess Safety S | harePoint | |
| | SharePoint site to access FAQs and guides. | | site | | | | |
| | | | To access the Pr | ocess Safety Share | ePoint site | | |
| | To access the Process Safety SharePoint site, | | Go to 'The Mark' homepage | | Consolidate to the second leading to the sec | | |
| | go to 'The Mark' homepage, scroll to the | | https://conocophilips.sharepoint.com/sib | es/The/Mark | The control of the co | | |
| | bottom, and click on 'ABU East OMS'. | | Scroll to the end of that homepage | ge, and click into 'ABU East OMS' | Electrical | | |
| | | | Register (Mark Face of Control of | and the second s | Secretary Secret | | |
| | | | | - / | 007-00 007-00 007-00 007-00 007-00 007-00 007-00 007-00 | | |
| | | | See Committee | MARIA A PA | ments me | | |
| 12. | Let's check what you have learned so far. | 1. What do you think is the purpose of Management of | Display OST | | | | |
| | Select the correct option and submit. | Change? | MCQ | | | | |
| | , | a) To manage HS&E risks associated with changes to plant, | Answer is in | bold. | | | |
| | | people and procedures | | | | | |
| | | ji i realization | I . | | | | |

| | b) To ensure risks associated with changes are identifi managed and mitigated c) To ensure risks associated with change are identified managed throughout the lifecycle of the change d) All of the above | That's correct. |
|--|--|---|
| 13. There are four categories involved Management of Change at ABU. categories has its own procedure provides guidance on executing the respective MOC processes a all COP employees and contracted any COP ABU-operated facility. Select each category to learn more | Each of these e, which and managing Ind applies to ors working at Standard Engineering Change (SMOC) (Go to 040) Operational Deviations (ODMOC) (Go to 050) Short Term Inhibits Register Document Change (DMOC) (Go to 060) Organisational Change (ORGMOC) for HSE Risks (G | That's incorrect. Tab Activity This is the landing screen. Build below given clickable flowchart in sync with VO. When learner clicks a tab, they are taken to a new screen (In the bracket of bullet points OST) with corresponding information. The learner must click on each tab before this topic is completed. |
| | Select each category to learn more. | ABU Management of Change Change (ORGMOC) Note: Text in the bracket not to be displayed on the screen |

| Topic | Management of Change (MOC) Awarene | ess for Downstream Operations (DSO) | Screen type | Blended | |
|-----------|---|-------------------------------------|--|---------------------------------|--|
| Screen Ti | tle Standard MOC (SMOC) for Engineering Co | hanges | Screen number | 040 | |
| No. | Audio/VO | On Screen Text | Visuals and Development instructions | | |
| 1. | Before diving into the Standard MOC, let's learn more | Why SMOC is important? | Display OST. | | |
| | about the event that highlighted its importance. | | Typography | | |
| 2. | On June 1, 1974, during a routine inspection at the Nypro | Flixborough Explosion (1974), UK | Refresh screen. | | |
| | chemical plant in Flixborough, in the rural part of | | | image (in black and white) in | |
| | Northern England, | | sync with 1 st para of | VO. | |
| | reactor 5 was found to have developed a crack. To | | S. S. Marine | | |
| | address this issue, production was halted, and reactor 5 | | 0 | | |
| | was removed for repairs. | | | | |
| | was removed for repairs. | | N. Committee of the com | | |
| | | | J.Har. | | |
| | | | · · · · · · · · · · · · · · · · · · · | | |
| | | | " uttersteet | | |
| | | | s s | | |
| | | | * * * * * * * * * * * * * * * * * * * | MIC II SOCIAL | |
| | | | shutterstsck: 2283250743 | standed to the seri | |
| | | | | age like the images given below | |
| | | | in sync with 2 nd para | = = = | |
| | | | | | |
| | | | ASTROOMS | BURS A ALETTES | |
| | | | 111112 | | |
| | | | THE REAL PROPERTY AND ADDRESS OF THE PERSON NAMED IN COLUMN TWO IN COLUMN TO THE PERSON NAMED IN COLUMN TWO IN COL | P ₁ | |
| | | | THE TANK | _ t in a | |
| | | | | JH. LIT | |
| | | | 新闻图画图 | | |
| | | | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | | |
| | | | 图 图 图 | 、目、目、肾、 | |
| | | | 一. 國際和 | | |
| | | | (For reference only) | | |

| | | OFF GAS |
|----|--|---|
| | | (For reference only) |
| 3. | To maintain operations, a temporary bypass pipe was installed to link reactors 4 and 6 together. This bypass consisted of a 20-inch steel pipe with flexible ends. To support the weight of the pipe, a nest of scaffolding was erected beneath it. | Refer slide 6 for image. Fade in image. Zoom on bypass pipe in sync with 1st para of VO. Zoom out from the pipe to show scaffolding in sync with 2 nd para of VO. |
| 4. | Unfortunately, the temporary bypass pipe was not adequately tested for the high pressures and mechanical stress it would face. This oversight led to a catastrophic failure, resulting in a massive explosion that devastated the plant, injured 36 people and claimed 28 lives. What do you think would have led to such a disaster? | Refer slide 6 for image. Fade out the image. Fade in the image in sync with VO. |

| 5. | The plant modification occurred without full assessment of the potential consequences: Modification went through no formal design or testing process No comprehensive Integrity calculations conducted of Bypass arrangement No pressure testing was carried out on the installed pipework modification No adequately engineered pipe supports of the bypass line (scaffold used) Maintenance Procedures not followed Design Codes for pipework not adhered to, including the use of flexible pipes | Key Findings: Modification went through no formal design or testing process No comprehensive Integrity calculations conducted of bypass arrangement No pressure testing was carried out on the installed pipework modification No adequately engineered pipe supports of the bypass line (scaffold used) Maintenance procedures not followed Design codes for pipework not adhered to, including the use of flexible pipes | Retain the screen. Blur the image. Display OST in sync with VO. |
|----|---|--|---|
| 6. | | Poor management & control of changes to plant and process increase risk to plant people and environment. | Refresh screen. Typography: Highlight with a bold font and a different colour. Use a border or background shading to make OST stand out. |
| 7. | Standard Engineering Change applies to any change to process, chemicals, technology, or equipment, as specified by current design and / or specifications except for a change that is a like-for like replacement. | Standard Engineering Change applies to any change to: Process Chemicals Technology Equipment Standard Engineering Change does not apply to like-for-like replacements. | Refresh screen. Display OST along with their respective icons in sync with VO. 2481035915 2427247103 |

| | | | 1907618299 |
|----|--|--|--|
| | | | |
| | | | 161727344 |
| 8. | Before exploring some Standard Engineering MOC examples, let's look at the WHRU project executed under an approved SMOC. | WHRU project executed under an approved SMOC | Display OST and the image. |
| 9. | Examples of engineering changes include, but are not limited to: Additions or modifications to process plants. Changes to equipment or piping materials. Maintenance repair work that expands to become a modification. Changes to the design basis. Introduction or removal of temporary equipment. Conversion of temporary equipment to permanent equipment. | Standard Engineering MOC Examples Additions/modifications of process plant Changes to equipment/piping materials Maintenance repair work that expands to become modification Change to design basis Introduction/removal of temporary equipment | Retain the screen. Move the image to the left side of the screen. Display OST on the right side in sync with VO. |

| | Changes to the type or amount of chemical additives Changes requiring revision to plant technical information / P&ID's Changes to facility throughput or feedstocks or product outside of unit design specifications Changes to set points or operating limits, including pressures, temperatures, densities, flow-rates, etc, which are different from ranges designated in the original safe operating limits, mechanical design | Conversion of temporary equipment to permanent equipment Changes to the type or amount of chemical additives Changes requiring revision to plant technical information/P&ID's Changes to facility throughput, feedstocks, or product that fall outside unit design specifications Changes to set points or operating limits (pressures, temperatures, densities, flow-rates, etc.) that differ from the original safe operating limits and mechanical design | Images |
|-----|---|--|--|
| 10. | For more information, refer to document: ABUE-000-SF- N05-C-00005: Engineering Management of Change Procedure | Refer to document: <i>ABUE-000-SF-N05-C-</i> 00005: Engineering Management of Change Procedure | |
| 11. | The Standard Engineering MOC (SMOC) process flow diagram provides an overview, with the following points detailing each step. Click on the icons to learn more. Click on the link for a quick view highlighting SMOC workflow and key steps at each phase. | Standard Engineering MOC (SMOC) Process Flow Initiate Evaluate Execute Document & Close out Click on the icons to learn more. Click on the link for a quick view highlighting SMOC workflow and key steps at each phase. | Display OST in sync with VO. Refer slide 8. Tab activity. Display OST and their respective icons in sync with VO. When a tab is clicked, it expands to open into a popup box with a close (X) button on the top-right corner. 16889520 10482770 22277916 13697051 |
| | | pridace | 19 (for 1 st 92 (for 2 nd 81 (for 3 rd 36 (for 4 th bullet bullet bullet bullet point) point) point) |

| | Initiate | | | | | |
|-----|---|--|--|--|--|--|
| 12. | At initiation, the proposed change is submitted for review and approval. The finalised design and all affected design documentation/plant information / records and drawings are updated and attached to reflect the proposed change at Initiate phase. | The proposed change is submitted for review and approval. The finalised design, along with all affected design documentation/plant information/records, and drawings, is updated and attached to reflect the proposed change. | | | | |
| | | Evaluate | | | | |
| 13. | In evaluate phase, the risk assessment requirements are assessed before relevant disciplines are required to technically review and approve the SMOC prior to the Engineering Manager formally approving Construction to commence. | Before construction can commence, the evaluation stage must be completed. This involves ensuring that all relevant disciplines have reviewed and endorsed the change, and that the Engineering Manager's Approval to Construct is secured. | | | | |
| | | Execute | | | | |
| 14. | Construction is completed with all start-up requirements met & PSSR completed prior to site management (the GFM) formally approving Start Up of the implemented change. Upon start-up of an SMOC, the change owner must ensure the start-up date is recorded in SAP and outstanding post start-up PSSR actions assigned, with all remaining redlines submitted within 48 hrs of change implementation | Once construction is completed and prior to start-up, the change owner must ensure the PSSR requirement step is completed. The PSSR is important to ensure the facility is ready for safe start-up and ongoing operations. As the change owner, you must also ensure the start-up date is formally recorded. | | | | |
| | Implementation | Document & Close Out | | | | |
| 15. | This is the final phase of the change, where all documentation is managed and plant information is updated to reflect the change. The change owner is responsible for ensuring the MOC progresses through the closeout process, verifying that all post start-up actions are completed and all document update tasks are confirmed as complete. | All documentation is managed, and plant information is updated to reflect the change. The change owner is responsible for ensuring the MOC progresses through the closeout process, verifying that all post start-up actions are completed and all document update tasks are confirmed as complete. | | | | |
| | | Activity Ends | | | | |

| 16. | The SMOC process for temporary engineering changes follows the same steps as permanent changes, but the change is authorised for only as long as the situation warrants. Temporary changes may incur a higher level of short-term risk; therefore, appropriate risk mitigation measures must be identified and implemented in order to manage the short-term risk. | Temporary SMOC Change Click the photo to learn more about temporary changes. Higher Short-Term Risk Identify and implement Risk Mitigation measures | Display OST and the image. shutterstock 1430400629 Place the photo horizontally and show the instructional text below it. When the learner clicks the photo, reveal the bullet points below the photo as shown in sync with the audio. Photo Click the photo to learn more about temporary |
|-----|---|--|---|
| | | | changes. • • |
| 17. | Ongoing monitoring and a strict extension process is in place to manage the temporary change until it is either reversed or made permanent, thus minimising risk at all times. | Before the authorised temporary change implementation period expires, one of the following must occur: • The system must be returned to its original condition/reversed | Display OST. A 'Temporary SMOC Example' button will be shown at the end. |
| | Let's take a look at some examples of Temporary SMOC. Click on the Temporary SMOC Examples button to learn more. | The MOC must be made permanent, with affected documentation updated and approval from discipline leads/approving authorities obtained The change extended via escalated approvals through Operations Management | The user will be able to click the button to see the information below in a pop up with a close button. Temporary SMOC Examples |

| | | Click on the Temporary SMOC Examples button to learn more. | Use of a temporary effluent tank and associated piping whilst replacing the permanent tank Use of temporary equipment for purging for shutdown or startup of equipment. Trial involving the Installation and Operation of wireless pressure transmitters Temporary isolation of a drain line by spading with a flange until repaired Trial lube oil compressor alternative cooler belt type Any temporary additions such as piping, utility |
|-----|---|--|--|
| | | | connections, or electrical equipment or connections |
| 18. | Here's the FLNE New Gangway executed under an approved SMOC. Now, let's look at one more event that highlights importance of SMOC. | FLNE New Gangway | Display OST and the image. |
| 19. | In 2001, a catastrophic failure occurred at the Humber Refinery due to a ruptured pipe. The rupture released a massive cloud of ethane/propane, which ignited, causing a massive explosion and fire. | UK Humber Refinery Explosion & Fire (2001) | Refresh screen. Display OST and the image in sync with VO (1st para). 1668330391 |

Fortunately, it happened on a public holiday, so there were no fatalities, but buildings up to 400 meters away were badly damaged.

The incident was caused by the installation of a new water injection point in an overhead gas pipe to prevent fouling. This "quick fix" job used the existing vent valve to connect the water, causing erosion of the downstream piping and eventual hole through.

The water injection point was installed without any Management of Change (MoC) process which would have reviewed the technical and safety aspects of the proposed change, identifying the corrosion risk introduced by the change /new injection point.



Fade out image.



(Refer slide 11) Fade in above image in sync with VO $(2^{nd} para)$. Fade out image.



(Refer slide 11) Fade in above image in sync with VO (3rd para).

Fade out image.



(Refer slide 11) Fade in above image in sync with VO (4th para).
Fade out image.



| 20. | | An effective MOC system is essential to ensure that process changes and/or facility | (Refer slide 11) Fade in ((5th para). Refresh screen. Typography: | above imag | e in sync with VO |
|-----|---|---|---|---------------------------------------|---|
| | | modifications do not compromise the safeguards built into the design or introduce new, unknown hazards. All technical and safety aspects of a proposed change are assessed before implementation. | Highlight with a bold for Use a border or backgrostand out. | | |
| 21. | Let's check how well you have grasped the concepts. | 1.Can you identify whether these statements are examples of Standard MOC or Like for Like? | Question Text | Standar d MOC | Like for Like |
| | Select the radio buttons to mark the | Select the radio buttons to mark the statements either Standard MOC or Like for | Changes to equipment, piping or their materials. | | |
| | | Like and Submit | Bolts, gaskets and flanges meeting the piping specification. | | |
| | | | Additions/modifications of plant equipment, process and associated systems. | | |
| | | | Right answer: That's correct. | | |
| | | | Changes to equipment, pand additions/modificat processes, and associate Standard MOC. Bolts, gathe piping specification a Like. | ions of planed systems a skets, and f | t equipment, are examples of langes meeting |
| | | | Wrong answer: That's incorrect. | | |

| 22. | 2.Prior to commencing | MCQ |
|-----|--|--|
| | construction/execution, whose approval to | Answer is in bold. |
| | construct is required? | |
| | (a) None | Right answer: |
| | (b) Engineering Manager | That's correct. |
| | (c) Operations Start-up Approval | |
| | | Prior to commencing construction/execution, the |
| | | Engineering Manager's approval to construct is |
| | | required. |
| | | ' |
| | | Wrong answer: |
| | | That's incorrect. |
| 23. | 3. Who is accountable for ensuring the | MCQ |
| 23. | relevant SAP MOC workflow tasks are | Answer is in bold. |
| | completed before execution or start up | 7 HISWEL IS III BOIG. |
| | commences? | Right answer: |
| | (a) Discipline Leads, who technically | That's correct. |
| | review and approve the change | That's correct. |
| | proposal | The Change Owner/MOC Coordinator is |
| | (b) The Change Owner/MOC | accountable for ensuring that the relevant SAP MOC |
| | Coordinator | = |
| | | workflow tasks are completed before execution or |
| | (c) Engineering Manager | startup commences. |
| | | Wrong answer: |
| | | That's incorrect. |
| 24. | 4. Before starting up an SMOC, the change | MCQ |
| | owner must ensure the following | Answer is in bold. |
| | requirements are met? | |
| | (a) Operations start-up approval | Right answer: |
| | obtained from GFM | That's correct. |
| | (b) PSSR completed | |
| | (c) Both a and b | Before starting up an SMOC, the change owner |
| | | must ensure that the Operations start-up approval |
| | | is obtained from GFM and that the PSSR is |
| | | completed. |
| | | completed. |
| | | Wrong answer: |
| | | That's incorrect. |
| | | mut s incorrect. |

| 25. | Let's check your understanding further. | 5.Can you identify when do you need to perform a PSSR? | Question Text | PSSR Required | PSSR Not Required |
|-----|---|---|--|---|-------------------------------|
| | | Select the radio buttons to mark the statements either PSSR Required or PSSR Not Required and Submit. | Any physical change or modification is made to the facility. Returning a temporary change to original design. Starting up decommissioned equipment. Right answer: That's correct. A PSSR is performed was modification is made to a temporary change to when starting up decommissioned equipment. | then any physio the facility, o the original co | when returning lesign, and |
| 26. | | 6.Upon start-up of an SMOC, the change owner must ensure the following requirements are met? (a) The Start-Up date recorded (b) All remaining redlines submitted within 48 hrs of change implementation (c) Both a and b | That's incorrect. MCQ Answer is in bold. Right answer: That's correct. Upon start-up of an SN ensure that the start-uremaining redlines are change implementation. Wrong answer: That's incorrect. | ip date is reco submitted wi | rded and all |

| Topic | | Management of Change (MOC) Award | eness for Downstream Operations (DSO) | Screen type | Blended |
|--------|---------------------------------|---|--|--------------------------------------|--|
| Screen | Title | Operational Deviations MOC (ODMOC |) | Screen number | 050 |
| No. | Audio/\ | /0 | On Screen Text | Visuals and Development instructions | |
| 1. | uncontr processe past ind | olled deviations to equipment, es, and procedures have been linked to ustry incidents, often due to sing deviations or failing to manage | Uncontrolled deviations to equipment, processes, and procedures have been linked to past industry incidents. These incidents often involved normalising deviations or failing to properly identify and manage the associated risks. | | hillips Manage of the separate esive image in sync with VO. |
| 2. | normal (| ng changes and their associated risks to operation is crucial for process safety key part of the Operating Integrity ork. | Managing operational deviations is a key part of the Operating Integrity Framework. | Display OST in syn | c with VO. |

| | | | 2413694241 |
|----|--|---|--|
| 3. | The Operational Deviation MOC process identifies, records, manages, and mitigates operational risks and temporary changes during normal day to day running of plant operations. | Operational Deviation MOC Process Identify Record Manage Mitigate Operational Risks Temporary Changes Deviations Normal Plant Operations | Create a word cloud in sync with VO. |
| 4. | Operational Deviations may be in the form of: Impaired Safety Critical Element which does not meet their Performance Standard. Inhibiting or bypassing a Safety Critical Element for maintenance and operations activities. Bypassing or bridging of non-safety critical hardware or software Use of Maintenance Overrides Deviations from established HSE, Maintenance or Operating Procedures Competency to Operate risks. | Operational Deviations may be in the form of: Impaired Safety Critical Element which does not meet their Performance Standard Inhibiting or bypassing a Safety Critical Element for maintenance and operations activities Bypassing or bridging of non-safety critical hardware or software Use of Maintenance Overrides Deviations from established HSE, Maintenance or Operating Procedures Competency to Operate risks | Display OST in sync with VO. Infographic |
| 5. | Let's take a look at the Operational Deviations (ODMOC) process flow, which provides an | Operational Deviations (ODMOC) Process Flow | Refer slide 17. |

| | overview, with the following points detailing each step. | ExecuteDoc & Close out | Create a clickable infographic. OST will appear on the same screen. |
|----|--|--|--|
| | Click on the icons to learn more. | Click on the icons to learn more. | COREM IPSUM Loren spum dolor is amet, con section adjacting etc. Care gave duting manifestion and considered adjacting etc. Care gave duting manifestion and considered adjacting etc. Care gave duting and considered adjacting etc. Care gave duting and considered adjacting etc. Care gave duting and considered etc. Care gave duting an adjacting etc. Care gave duting and etc. Care gave duting gave duting and etc. Care gave duting gave gave duting gave duting gave duting gave duting gave gave duting gave gave gave duting gave gave gave gave gave gave gave gav |
| | | | 16889520 10482770 22277916 13697051 19 (for 1st 92 (for 2nd bullet bullet bullet point) point) 13697051 point) |
| | | Initiate | |
| 6. | | Recognise deviation/faulty equipment/force/inhibit Determine if the equipment is safety critical or not Raise ODMOC, select ODMOC category, conduct a risk assessment, and verify controls | |
| | | Evaluate | |
| 7. | | Risk Assessment Approval (Relevant TA) Verify risk assessment and mitigation measures to reduce risk adequate | |
| | | Execute | |
| 8. | | ODMOC Approval to Place into Operation (hierarchical approvals based on residual risk rating) Record Start Up Date | |
| | | Doc & Close out | |

| 9. | | Deviation Close-out/Removal | | | | |
|-----|--|---|--|--|--|--|
| | | Activity Ends | | | | |
| 10. | It's Important to highlight that ABU utilises two tools for Force / Inhibit management: SAP MOC (ODMOC) & the Electronic Short Term Inhibits (STI) Register depending on the type of force / inhibit and its application. | ABU utilises two tools for Force/Inhibit management: SAP MOC (ODMOC) The Electronic Short Term Inhibits Register | Display OST and the image in sync with VO. Refer Slide 28 | | | |
| 11. | The STI register is intended to assist with management of routine planned low risk inhibits of short duration (within a shift duration) to facilitate short term troubleshooting or planned maintenance activities such as routine building fire and gas detection testing. Inhibits extending beyond a shift duration or greater than a RR Score of 4 must be raised as Operational Deviations | The STI Register applies to inhibits that meet the following timeframe and risk criteria: • Expected to last less than a shift duration • Classified as low residual risk (RR 4) Inhibits extending beyond a shift duration or greater than a RR Score of 4 must be raised as Operational Deviations. | Retain the screen. Display OST in sync with VO. | | | |
| 12. | Let's look at some Short Term Inhibit Examples and Exclusions. Click on Examples and Exclusions to learn more. | Short Term Inhibit | Tab activity When a tab is clicked, it expands to open into a popup box with a close (X) button on the top-right corner. | | | |
| | Examples | | | | | |
| 13. | | ½ hr outage of FWM to repair a valve Investigate/repair level transmitter < shift Monthly Building F&G detection Repair/Calibrate Faulty Tx Inhibit Fire Suppression System to enable core idle inspections less than a shift duration | | | | |

| | | Opening manual bypasses around a control valve to allow a control valve or shut-off valve (XV) to be stroked Erratic Gas Detector ½ hr Outage of fast response vehicle LT MOS to inhibit interlock to allow final element CFT stroke test of XV | |
|-----|--|--|---|
| 14. | | Exclusions A Loyal Transmitter MOS extends beyond | |
| 14. | | A Level Transmitter MOS extends beyond shift duration as troubleshooting revealed fault requiring repair MOS to 0HV-24094 to open/close valve as part of isolation requirements whilst maintenance carried out on 0LA-2402 (exceeded shift duration) GE Force on 2TC1421 to prevent step to idle (not routine, exceeded shift duration) Apply MOS to LT for SDP Investigation (not routine, Med Risk) | |
| | | Activity ends | |
| 15. | After reviewing STI examples and exclusions, let's examine the Operational Deviations Risk Assessment. Operational Deviations can only be approved once effective mitigation measures to reduce the risk associated with the deviation have been identified and the residual risk of operating with the deviation is reduced as far as reasonably practicable (SFARP). Operational Deviation Risk Assessments require a minimum number of attendees. | Approve Operational Deviations only after these conditions are met: • Identify effective mitigation measures to reduce the risk associated with the deviation • Ensure the residual risk of operating with the deviation is reduced SFARP Require a minimum of two attendees: • Operational Deviation Change Owner • Operations Representative (note, an Operations Specialist is required for residual risks rated as medium or greater) • Relevant discipline engineers/specialists should be engaged as appropriate or required | Retain the previous screen in sync with 1st VO. Fade out. Fade in header and the image in sync with 2nd VO. RISK ASSESSMENT AND THE IHOOO 2508667763 Display highlighted OST as two column headers and the rest of the OST in sync. |

| 16. | The risk assessment for an Operational Deviation will therefore be required to be reviewed and endorsed by a Technical Authority or delegate in line with the Type/Category of the Operational Deviation, as the examples shown in the table. | For example, an SCE related deviation will automatically assign a Process Safety Engineer as the risk approver / technical authority whereas a Temporary Software force deviation will require automation approval. | An information icon will be shown at the end of the table. The user will be able to click the icon to see the information below in a pop up with a close button. SCE deviations shall always have safety consequence assessed in addition to any other Hazards identified. |
|-----|---|---|---|
| | | | A 'Note' button will be shown at the end of OST 'Process Safety Engineer'. The user will be able to click the button to see the information below in a pop up with a close button Note: The Process Safety Engineer may engage the Relief TA's approval if the SCE ODMOC involves alt relief paths/reduced depressuring capacity. |
| | | | A 'Deviation Approval' button will be shown at the end of the table. The user will be able to click the button to see the information below in a pop up with a close button. Once the risk assessment is reviewed and endorsed by the relevant TA, the ODMOC requires Operations approval to be formally placed into operation. The level of approval required to operate with the Operational Deviation is hierarchical and will vary depending on the residual risk ranking assigned during the risk assessment process. Deviation approvals are embedded within the workflow and |
| 17. | The ODMOC risk assessment must assess the most credible risk associated with operating | | are in line with ABU risk management guidelines. Animate a magnifying glass moving on each risk for the entire VO. |

| | with the Operational Deviation in place and to identify mitigating controls (active/required) to reduce the risk SFARP. | | Herestrody Stuffers St. Stuffers St. Stuffers St. |
|-----|--|---|---|
| 18. | Now let's look at an event that highlights importance of ODMOC. | Why ODMOC is important? | Typographhy |
| 19. | At Buncefield (UK) in 2005, during gasoline storage tank fill operations, safety systems failed, releasing 300 tonnes of gasoline over 30 minutes. Flammable vapours spread 250 meters around the tank and ignited, causing a powerful explosion that devastated the fuel depot. The incident, occurring on a Sunday morning, resulted in 43 injuries but no fatalities. The key issues were that the automatic tank gauging system on the tank was faulty, and an independent high-high level switch installed in July 2004 was left inoperable following testing. Proper overfill protection could have prevented the incident. This highlights the importance of recognizing and managing risks through the Operation Deviation MOC process. | Key Issues: The automatic tank gauging system on the tank was faulty An independent high-high level switch installed in July 2004 was left inoperable following testing There was a normalisation of deviation at the facility with no risk assessment or mitigation of the impaired tank gauging system | Refresh screen. Display OST (Buncefield Explosion, UK (2005)) and the upper part of the image with camera spanning from top to bottom slowly in sync with 1 st para of VO. Fade out the image. Fade in the image given below in sync with 2 nd para of VO. |

| 20. | | Recognising impaired equipment and formally | | shutterstyck 2528480339 Blur the image and show O para of VO. Refresh screen. | ST in sync | with 3rd | interfective constraints of the second secon |
|-----|--|---|----------------|---|-------------|-----------|--|
| 20. | | assessing risks and controls required to manage | e risks | Typography: | | | |
| | | is important and at ABU is managed via ODMO | | Highlight with a bold font o | and a diffe | rent colo | our. |
| | | | | Use a border or background stand out. | d shading | to make | OST |
| 21. | Let's explore the differences between Temp SMOC (Engineering/Physical change) and ODMOC (Plant Operational Risks). | Temp SMOC (Engineering/Physical change) | ODM | OC (Plant Operational Risks) | | | |
| | | Temp additions/modifications of plant equipment systems | Impai | red Safety Critical Element | | | |
| | | Temp changes to equipment/piping materials | Opera windo | tion outside of procedures/o ws | perating | | |
| | | Temp change to design basis | | orarily operating with ted/bypassed equipment | | | |
| | | Introduction/removal of temporary equipment | _ | ge in normal process plant op guration | erating | | |
| 22. | Let's assess how well you understand these | 1.Can you identify whether these statements a examples of Temporary SMOC or ODMOC or Sh | | | | | |
| | concepts. | Term Inhibits Register? | iioit | | Temp | ODM | STI |
| | | | | | SMOC | OC | Registe |
| | | | | | | | r |

| | Use of temporary hire |
|---|---|
| Select the radio buttons to mark the statements | compressor hooked into |
| either Temporary SMOC or ODMOC or Short Term | plant |
| | · |
| Inhibits Register and Submit. | Temporary install of a |
| | pipe clamp |
| | Application of an |
| | override or bypass for |
| | maintenance activities |
| | that is of Low RR and less |
| | than a shift duration. |
| | Safety related shutoff |
| | valve operating slower |
| | than design |
| | |
| | Maria |
| | Wrong answer: |
| | That's incorrect. |
| | You may have answered either all or some of them |
| | incorrectly. If you are unclear about any of these |
| | statements, please review the content before moving |
| | on. |
| | |
| | Right answer: |
| | That's correct. You got all of them right. |
| | The use of a temporary hire compressor hooked into |
| | the plant would be an example of Temporary SMOC, |
| | as it involves the introduction of temporary |
| | equipment that alters the process plant's |
| | configuration, albeit for a short duration. Temporary |
| | measures like these require careful evaluation and |
| | adherence to safety protocols to ensure no adverse |
| | impact on the plant's operations or ignition risks. |
| | Ensuring that the temporary compressor meets all |
| | safety and operational standards is crucial before |
| | integrating it into the plant. Documentation and |

| | proper authorization are also necessary to track this change and revert to the original configuration after its use. The temporary installation of a pipe clamp is also an example of Temporary SMOC. The application of an override or bypass for maintenance activities that is of Low RR and less than a shift duration is an example of an STI register. A safety-related shutoff valve operating slower than design is an example of ODMOC, which ensures operating risk is managed and visibility exists until repaired. |
|---|---|
| Select the correct statement with regards to ODMOC risk assessment: (a) A minimum of two risk assessors are required for ODMOC: Operational Deviation Change Owner Operations Representative (b) An Operations Specialist is required for residual risks rated as medium or greater. (c) Relevant discipline engineers/specialists should be engaged as appropriate or required (d) All of the above are correct requirements | MCQ Answers are in bold. Wrong answer: That's incorrect. Right answer: That's correct A minimum of two risk assessors are required for ODMOC: an Operational Deviation Change Owner and an Operational Representative. An Operations Specialist is required for residual risks rated as medium or greater. Relevant Discipline engineer or specialist can be engaged as required. |
| <go 030-13="" to=""></go> | |

| Topic | | Management of Change (MOC) A | wareness for Downstream Operations (DSO) | Screen type Blended | |
|----------|-------------------|--|---|--------------------------|----------------------|
| Screen T | itle | Document MOC (DMOC) | | Screen number | 060 |
| No. | Audio/VO | | On Screen Text | Visuals and Deve | lopment instructions |
| 1. | _ | es include alteration to any new or d document or procedure. | Alterations to new controlled documents Alterations to existing controlled documents or procedures | shutterstsck: 2315954947 | MAGE 10. 2319524 |
| 2. | to ABU Functional | nents include, but are not limited I Team procedures, associated Forms, Standards or Manuals. | Controlled Documents include: ABU Functional Team Procedures Check Sheets and Forms Standards or Manuals | | 7599 |
| 3. | departmental pro | is not limited to, any changes to cedures or facility operations as electronic operating documents ions. | Changes include • Departmental procedures • Facility operations procedures (electronic operating documents and work instructions) | Display OST in syr | nc. |

| 1 | Let's look at examples when Document MOC is | | | Create a click | rable infoara | nhic OST will | appear on the |
|----|--|--|---|---|---|---|---|
| 4. | required and events that do not invoke DMOC. Click on each section to learn more. | Examples: Document MOC is required | Events: Document MOC is not invoked | same screen. | | orne. OST WIII | uppear on the |
| | | Click on each section to | o learn more. | | | | |
| | | Examples: Document | MOC is required | | | | |
| 5. | | new section If an existing revised to re and/or conditi If there is a ch | d document requires a g section needs to be eflect current practises ons ange to a procedure that activity is performed | | | | |
| | | Events: Document Mo | OC is not invoked | | | | |
| 6. | | changes to do Change to a sa setting or processafe operating extended (Eng Temporary Op procedure (Op | ife operating limit, trip sedure that requires a limit (SOL) to be sineering MOC) eration outside of a perational Deviation) anned maintenance or | | | | |
| | , | Activity 6 | | | | | |
| 7. | The Document Management of Change (DMOC) process flow diagram provides a clear overview of its workings. Let's break down each step to get a better understanding. | Document Manageme Process Flow • Initiate | nt of Change (DMOC) | | | phic. As the levealed on the | sarner clicks on same screen. |
| | Click on the icons to learn more. | Evaluate Execute Documentatio Click on the icons to le | | 16889520 19 (for 1st bullet point) | 10482770 92 (for 2 nd bullet point) | 22277916 81 (for 3 rd bullet point) | 13697051 36 (for 4 th bullet point) |

| | Initiate |
|-----|---|
| 8. | Change Owner initiates a DMOC for new/amendment/deletion Selects document type and discipline, which auto-assigns the relevant discipline reviewer in the workflow As the initiator, the change owner understands that they cannot also be the reviewer |
| | Evaluate |
| 9. | Based on the document type and discipline, a Discipline Specialist is assigned to review/endorse the change and determine/assign additional discipline reviews or risk assessment requirements. Reviewers add their comments to the document under the review task before the change owner finalises the document. If nominated, a risk assessment is conducted after discipline reviews have been completed and the document has been updated with their comments. The change owner identifies whether additional training is required and nominates no/formal/informal training as needed. |
| | Execute |
| 10. | Document Approval |
| | Documentation & Close-out |
| 11. | The Document Controller publishes the finalised controlled document as 'Issued for Use' in the relevant repository (ODMS or MyAP (Aveva). |
| | Activity ends |

| 12. | Each DOCMOC submission will invoke a Discipline Specialist to review & approve the change or new document. The discipline specialist is auto assigned based on MOC document discipline and has the opportunity to seek a risk assessment or additional reviewers for the MOC. Following this, a final approver is engaged to endorse the change, verifying all necessary reviews have been conducted. | Discipline Specialist Review & approve Seeks DOCMOC submission Risk Assessment/Reviewers endorses & verifies Final Approver | Create a flowchart. | |
|-----|---|---|--|------------------------|
| 13. | For more information, refer to Document Management of Change Procedure. | Refer to ABUE-000-SF-N05-C-0003: Document Management of Change Procedure | | |
| 14. | Now, let's check your understanding of events that invoke Document MOC. | 1.Can you identify which events invoke Document MOC? Select the radio buttons to mark Document MOC or Non Document MOC and Submit. | Display OST in sync with VO. Right answer: That's correct. You got all of them rig Wrong answer: That's incorrect. If you are unclear about any of these please review the content before mo | statements, |
| | | | Question Text Document MOC Typographical or administrative changes to a document. A new section added to a controlled document. | Non Document MOC |

| | | | A shanga to an |
|-----|---|--|----------------------|
| | | | A change to an |
| | | | operating |
| | | | procedure that |
| | | | alters how an |
| | | | activity is |
| | | | performed. |
| | | | Permanent change |
| | | | to an alarm setting |
| | | | (not a trip setting) |
| | | | within a SOL. |
| 15. | Let's check your understanding further. | 2.The role of the Discipline specialist, at the | MCQ |
| | | Evaluate stage, includes determining if a risk assessment is required for the proposed | Answer is in bold. |
| | | changes. | Right answer: |
| | | State whether this is true or false. | That's correct. |
| | | • True | Wrong answer: |
| | | • False | That's incorrect. |
| | | <go 030-13="" to=""></go> |] |

| Topic | Mana | agement of Change (MOC) Awareness | for Downstream Operations (DSO) | Screen type | Blended |
|----------|--|--|--|-------------------------------------|---|
| Screen T | itle Orga | nisational MOC (ORGMOC) | | Screen number | 070 |
| No. | Audio/VO | | ON SCREEN TEXT | Visuals and Deve | lopment instructions |
| 1. | 1. An effective Organisational Management of Change (MOC) system ensures that Health, Safety, and Environmental (HSE) risks associated with changes in critical positions are managed before, during, and after these key changes. | | An effective Org MOC system ensures HSE risks related to changes in critical positions are managed prior to, during and following key changes to HSE critical positions. | | bold font and a different colour. ackground shading to make OST stand |
| 2. | affecting HSE Critical Pos | lies to all ABU organisational changes sitions. managed via the Organisational MOC | ABU Organisational Changes to HSE Critical Positions → Managed via Organisational MOC Process | SE Build flowchart in sync with VO. | |
| 3. | | | Organisational MOC Modifications | (For | icons in place of icons in the image. |

| 4. | For more information regarding Organisational Management of Change Procedure, please refer to the document. | Refer to Organisational Management of Change Procedure Document: ABUE-000-SF-N05-C-00006 | (For 3 rd OST) (For 4 th OST) 2584464097 |
|----|---|---|---|
| 5. | Let's look at some examples of Organisational MOC. Click on the icons to learn more. | Organisational Management of Change Examples Click on the icons to learn more. Changes to individuals fulfilling HSE critical positions (personal replacement, reporting line changes, or substantive changes to responsibilities) Introduction, removal and/or consolidation of any individual HSE critical position Alteration to the organisational structure of an entire department or function* Alteration to the physical location where a department or functional group is based* *Includes non-HSE critical positions and functions | Refer slide 36 Build a clickable infographic. As the learner clicks on the icon, OST bullet points are revealed. Display OST (Organisational Management of Change Examples) at the centre of the infographic. 1. |

| 6. | The Organizational Management of Change (ORGMOC) process flow diagram gives you a good overview of how it all works. Let's dive into each process to understand it better. Click on the icons to learn more. | Organizational Management of Change (ORGMOC) Process Flow Initiate Evaluate Execute Doc & Closeout Click on the icons to learn more. | 2474188901 (4th bullet point) Display OST in sync with VO. Refer slide 37. Build the clickable infographic. As the learner clicks on the icon, the content is revealed. Lives from the first adjusting the Case per label with substitution and the clickable with the substitution of the content is revealed. 2478889679 2478889679 1688952 1048277 2227791 1369705 019 (for 092 (for 681 (for 1st bullet 2nd bullet 2nd bullet 2nd bullet 2nd bullet 2nd bullet 3rd bullet 4th bullet | | | | |
|----|--|---|---|--|--|--|--|
| | | | point) point) point) point) | | | | |
| | | Initiate | | | | | |
| 7. | | Initiate Organisational MOC | | | | | |
| | | Assessment Tool | | | | | |
| 8. | | Evaluate Determine Type of Change and Sponsor (minor/major/significant) Complete Organisational | d | | | | |
| | Execute | | | | | | |
| 9. | | Change Sponsor Approval of Org MOC | | | | | |

| | | 0.1010.010.0010.0010.001 | | | | | |
|-----|---|----------------------------------|--|--|--|--|--|
| | | Outstanding actions entered | | | | | |
| | | into integrated Risk | | | | | |
| | | Management System (IRMS) | | | | | |
| | Doc & Close out | | | | | | |
| 10. | | OrgMOC Checklist & Approval | | | | | |
| | | uploaded to ODMS | | | | | |
| | | Activity ends | | | | | |
| 11. | Let's examine a tragic event that underscores the critical | Why is Organizational Management | Display OST in sync with VO. | | | | |
| | importance of organizational Management of Change | of Change (ORGMOC) important? | Typography (same as 004-01) | | | | |
| | (ORGMOC). | | | | | | |
| 12. | In 1998, at the Esso Longford gas plant in Victoria, Australia, a | Esso Longford Explosion & Fire | Refresh screen. | | | | |
| | brittle fracture in a heat exchanger led to a catastrophic | (1998) | Refer slide 38. | | | | |
| | failure and rupture. | | Display OST and the image in sync with VO (1st para). | | | | |
| | | | | | | | |
| | This caused a significant loss of containment, resulting in a | | | | | | |
| | vapor cloud that ignited into a devastating explosion and fire. | Key Findings | | | | | |
| | The explosion claimed the lives of two workers and injured | Low temperature due to loss of | | | | | |
| | eight others. | lean oil | | | | | |
| | | Failure to conduct Org MOC for | | | | | |
| | Investigations revealed that the low temperature, caused by | relocating senior staff to head | | | | | |
| | the loss of lean oil, was a critical factor in the heat exchanger's | office several years earlier | | | | | |
| | failure and the failure to conduct an organisational | | ab. March all | | | | |
| | Management of Change (MOC) process when senior | | shutterstock | | | | |
| | engineering staff were relocated to the head office in | | 2234573753 | | | | |
| | Melbourne several years earlier. This oversight meant that | | District the investigation of the VO (200) | | | | |
| | crucial expertise was not available on-site, contributing to the | | Display the image in sync with VO (2 nd para). | | | | |
| | disaster. | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | Charles Constitution of the Constitution of th | | | | |
| | | | | | | | |
| | | | Blur the image. | | | | |
| | | | Display OST (2 nd) in sync with VO (3 rd para). | | | | |
| | | | Display 331 (2) ill sylle with vo (3 para). | | | | |

| 13. | Now, let's check your understanding of the types of change. | 1.Can you identify which type of change each statement belongs to? | | | | | |
|-----------------|---|--|---|--------------------------|----------|--------------------|--|
| | | Select the radio buttons to mark SMOC (Engineering Change), Operational Deviation, Document, or Organizational and Submit. | | | | | |
| | | Question Text | SMOC (Engineerin g change) | Operational Deviation | Document | Organizati onal | |
| | Temporary deviation from the way equipment is usually operated, according to established procedures or performance standards. | | | | | | |
| | | Changes to reporting relationships for HSE Critical Positions or staffing levels, individual HSE Critical roles that increase or change responsibilities or the consolidation of departments and service groups. | | | | | |
| | | Any maintenance that results in a modification, or temporary equipment which becomes permanent equipment. | | | | | |
| | | Any change to a controlled document such as a procedure. | | | | | |
| 14. | | Т | Wrong answer: That's incorrect. | | | | |
| incorrectly. If | | ncorrectly. If yo | u may have answered either all or some of them correctly. If you are unclear about any of these atements, please review the content before moving on. | | | | |
| | | F | ight answer: | | | | |

| | | That's correct. You got all of them right. | | | |
|---------------------------|--|--|--|--|--|
| <go 030-13="" to=""></go> | | | | | |

| Topic | | Management of Change (MOC) Awareness | for Dow | nstream Operations (DSO) | Screen type | Blended | |
|----------|----------|---|----------------------|---|--------------------|---|--|
| Screen T | itle | Quiz | | | Screen number 080 | | |
| No. | Audio/VO | | On Scr | een Text | Visuals and Deve | lopment instructions | |
| 1. | | us evaluate what you have learned with stions on the overall MOC intent and | | | using the image of | OPERATING INTEGRITY ASSET INTEGRITY | |
| 2. | | | 1. a) b) c) | Who does the MOC process apply to? Only COP ABU employees Only contractor employees All COP ABU and contractor employees involved in the operation, maintenance, engineering, or modification of processes or equipment None of the above | contractor emplo | s applies to all COP ABU and oyees involved in the operation, gineering, or modification of | |
| 3. | | | 2. a) | As a change owner what are my accountabilities? Overseeing the progression & maintaining compliance with the MOC SAP workflow and ensuring all MOC requirements & | compliance with | rogression and maintaining the MOC SAP workflow, ensuring all its and deliverables are met during | |

| | , | | <u></u> |
|----|--------------|-------------------------------|---|
| | | deliverables are met during | each phase, acting as the subject matter expert for the |
| | | each phase. | proposed change, ensuring the change is |
| | b) | Subject matter expert for | communicated, and confirming that appropriate |
| | | the proposed change | training of affected parties has been completed are a |
| | (c) | Ensures the Change is | change owner's accountabilities. |
| | | communicated, and | |
| | | appropriate training of | Wrong answer: |
| | | affected parties has been | That's incorrect. |
| | | completed | |
| | d) | All of the above | |
| 4. | 3. | What changes does | MCQ |
| | | OrgMOC apply to? | Answers are in bold. |
| | a) | HSE Critical Position | |
| | | Changes Only | Right answer: |
| | (b) | All Personnel Changes | That's correct. |
| | (c) | All positions acting in roles | OrgMOC applies only to HSE critical position changes. |
| | | | |
| | | | Wrong answer: |
| | | | That's incorrect. |

| Topic | | Course Completion Screen | | Screen type | | Image and Text | |
|--------|---------|------------------------------|--|---------------|--------------------------------------|-----------------------|--|
| Screer | n Title | Thank you | | Screen label | | 090 | |
| No. | Audio | /vo | ON SCREEN TEXT | Visuals and D | Visuals and Development instructions | | |
| 1. | Stando | ard course completion screen | Thank You and Congratulations! You have completed the Manageme Awareness Module. Process Safety is Everyone's respons | | Pr Pr | ocess Safety Matters. | |